



Mazhar Hajizadeh  
Gupta & Associates Inc.

Date: 12/22/2021

Project: City of Pflugerville Surface Water Treatment Plant Temporary Connections

We are pleased to quote the electrical work associated with connecting a 1000KW rental generator and a 1500KW rental generator as indicated on GAI drawing EXH-1 for the sum of \$58,800.00 without any provisions for Kirk Key interlocks as we do not know what will be required to attached to the (2) rental switches. This price includes the following:

**480V Generator**

Furnish and install 20' of cable with conduit or cable tray from the 1600A rental breaker to the existing 3000A Board.

Lugs, labor, and misc. materials to terminate the cables.

**5KV Generator**

Furnish and install 5KV cables, conduit, and a wall penetration from the 5KV rental switch to the existing 5KV Board.

Stress cones and misc. materials to terminate the cables.

Notes:

1. All rental equipment and rental wiring to be furnished and installed by others.
2. Both rental switches/breakers to be located as close to the existing gear as possible.
3. Removal of the temporary wiring is included in this quote.
4. Testing of all new cables is included in this quote.
5. The cost of a bond is included as I assume you are considering adding it to an existing contract by way of change order.

Thanks for the opportunity to provide this quote. If you would like us to do the work please let us know as soon as you can so that we can gather up the material. At this time all material that we will need is available but that may change as a result of the ongoing global pandemic. Please let us know if you have any questions or if you need any additional information.

Regards,

Michael Clasen

C.F. McDonald Electric

Project Manager