

## Change Order No. 7

Project Name: Kelly Lane at SH 130 NBFR Left Turn Lane Improvements	Owner's Project No.:
Project Owner and Address: City of Pflugerville 100 E. Main Street P O BOX 589 Pflugerville, TX 78691-0589	Date of Issuance: January 28, 2015
Project Contractor and Address: Cash Construction Company, Inc. 18607 Heatherwilde Blvd. Pflugerville, Texas 78660	Date of Contract:
	Contract Period:

It is agreed to modify the Contract referred to above as follows:

Item #	Description Of Changes	Deduct from Contract	Change in Contract Price	Change in Contract Time
1	Left Turn Lane and Traffic Signal Modification (See Attached Worksheet)		\$135,881.40	98 Days
Difference Net =		N/A	\$135,881.40	98 Days

Summary It is agreed to modify the Contract referred to above as follows:

Contract Price prior to this Change Order: \$ _____	Contract Time prior to this Change Order Substantial (days and date) _____ Final (days and date) _____
Net Increase (decrease) of this Change Order: \$ 135,881.40	Net Increase (decrease) of this Change Order 98 days
Revised Contract Price with all approved Change Orders: \$ _____	Revised Contract Time with all approved Change Orders Substantial (days and date): _____ Final (days and date): _____

The changes included in this Change Order are to be accomplished in accordance with the terms, stipulations and conditions of the original Contract as though included therein.

Accepted for Contractor by: Cash Construction Company, Inc.

1/28/15  
Date:

Recommended for Approval by: Dan Franz, P.E., City Engineer

1/28/15  
Date:

Approved for Owner by: Brandon Wade, City Manager

Attest: \_\_\_\_\_ Date:

Approved for Owner by: (Other - when required) \_\_\_\_\_

\_\_\_\_\_ Date:

Distribution: Contractor \_\_\_\_\_ File \_\_\_\_\_ Field \_\_\_\_\_ Owner \_\_\_\_\_ Other \_\_\_\_\_

<b>CONTRACTOR: CASH CONSTRUCTION COMPANY, LTD.</b>					
<b>PROJECT:</b>	Kelly Lane Phase 1 Muchison Ridge to Falcon Pointe Blvd (West)				
<b>ITEM:</b>	CPR #11 Kelly Lane Turn Lane				
<b>DATE:</b>	1/21/2015				
<b>Item #</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Additional Days</b>	<b>Unit Bid Amount</b>
	<b><u>New &amp; Additional Items</u></b>				
1	Remove & Dispose of 18" RCP	12.00	LF		\$120.00 \$1,440.00
2	Unclassified Roadway Excavation	191.00	CY		\$30.00 \$5,730.00
3	Unclassified Fill Embankment	37.00	CY		\$26.00 \$962.00
4	Traffic Control	1.00	LS		\$8,800.00 \$8,800.00
5	4" Single White Dashed TY II	66.00	LF		\$1.30 \$85.80
6	4" Double Yellow Solid TY II	582.00	LF		\$2.50 \$1,455.00
7	8" Single White Solid TY II	450.00	LF		\$2.50 \$1,125.00
8	24" Stop Bar TY II	12.00	LF		\$8.00 \$96.00
9	Traffic Signage	1.00	LS		\$2,400.00 \$2,400.00
10	4" Single White Dashed TY I	66.00	LF		\$1.30 \$85.80
11	8" Single White Dashed TY I	450.00	LF		\$2.60 \$1,170.00
12	4" Double Yellow Solid TY I	582.00	LF		\$2.60 \$1,513.20
13	24" Stop Bar TY I	12.00	LF		\$21.00 \$252.00
14	Elim Exist Pav Mrk & Mrks 4"	765.00	LF		\$1.40 \$1,071.00
15	Elim Exist Pav Mrk & Mrks 12"	198.00	LF		\$3.20 \$633.60
16	2" HMAC TY C	347.00	SY		\$25.00 \$8,675.00
17	4" HMAC TY B	491.00	SY		\$27.00 \$13,257.00
18	8" HMAC TY B	283.00	TN		\$79.00 \$22,357.00
19	6" Curb & Gutter	268.00	LF		\$29.50 \$7,906.00
20	6" Stamped Conc Pav in Medians (Brick Pavers)	219.00	SY		\$70.00 \$15,330.00
21	Remove, Relocate & Reset Exist Curb Inlet TY IL-c	1.00	EA		\$5,000.00 \$5,000.00
22	Remove Exist Conc Curb & Gutter	561.00	LF		\$12.00 \$6,732.00
23	Drill Shaft TRF Sig Pole 36"	14.00	LF		\$350.00 \$4,900.00
24	Condt PVC Shcd 40 2"	10.00	LF		\$45.00 \$450.00
25	Condt PVC Shcd 40 3"	10.00	LF		\$48.00 \$480.00
26	Elec Condr No 8 Bare	20.00	LF		\$8.00 \$160.00
27	Install WHY TRF Sig Isolated	1.00	EA		\$4,100.00 \$4,100.00
28	Back Plate 12" LED GRN	3.00	EA		\$75.00 \$225.00
29	VEH Sig Sec 12" LED GRN	3.00	EA		\$250.00 \$750.00
30	VEH Sig Sec 12" LED YEL	3.00	EA		\$250.00 \$750.00
31	VEH Sig Sec 12" LED RED	3.00	EA		\$250.00 \$750.00
32	TRF Sig CBL TY A 14 AWG 5 CONDR	600.00	LF		\$3.00 \$1,800.00
33	INS TRF SIG PL AM S 1 ARM 48	1.00	EA		\$10,200.00 \$10,200.00
34	Removing Traffic Signals Mast Arm	1.00	EA		\$1,300.00 \$1,300.00
35	VIVDS Camera Assembly	1.00	EA		\$2,000.00 \$2,000.00
36	VIVDS Communication Cable Coaxial	485.00	LF		\$4.00 \$1,940.00
	<b>Total</b>			<b>0.00</b>	<b>\$135,881.40</b>
<b>PRICES INCLUDE: BONDS, MOBILIZATION.</b>					
<b>PRICES EXCLUDE: SALES TAX, FIELD OFFICE, LAB TESTING, CONSTRUCTION PHOTOS, CONSTRUCTION VIDEOS, SURVEYING, ENGINEERING, PIN REPLACEMENT, PERMITS, FEES, CONCRETE REPAIR, HMAC REPAIR, PAVEMENT MARKINGS, ANY EROSION CONTROLS OR RESTORATION NOT LISTED.</b>					
<b>NOTE:</b>					

Project Duration Note: The duration of this change order is 98 Calendar Days (14 Weeks). This duration is based on 12 weeks for delivery of traffic signal equipment to site and 2 weeks to install new equipment and remove existing equipment. Turn lane improvements will be timed to be completed by the time the new signal equipment is installed.