

DCS Engineering, LLC  
1101 S. Capital of Texas Highway  
Building G-100  
Austin, Texas 78746  
  
Tel: (512) 614-6171  
T.B.P.E. Firm No F- 13162  
www.DCS-Engineering.com

March 14, 2022

Ms. Amy Madison  
Pflugerville Community Development Corporation  
3801 Helios Way, Suite 130  
Pflugerville, Texas 78660

Re: PCDC – Impact Way Extension Phase III A & B  
Recommendation to Award Contract  
DCS Project No. 20101482

Dear Ms. Madison:

On March 11, 2022, DCS Engineering (DCS) assisted PCDC in opening bids for the above referenced project. Two bid proposals were received with total bid prices ranging from \$2,382,550.50 to \$3,162,434.50. A tabulation of the bids received is attached. The budgeted amount for construction of this project was \$2,544,000. The low bidder is Joe Bland Construction, LP. from Austin, Texas with a bid of \$2,382,550.50. This is \$161,825 below the budgeted amount. It should be noted here that there will be an additional approximate cost of \$80,000 PCDC will be required to pay to Atmos and Oncor for the installation of dry utilities within the right of way as part of the 940 ft long road extension.

DCS has reviewed the Proposal and Bid Schedule including the required documents listed in the Instructions to Bidders to be submitted with the bid package by Joe Bland Construction, LP and found it to be accurate. However, two documents required to be included with the bid submission were submitted but were not correctly filled out. These were the Conflict of Interest Questionnaire and the Bidder's Questionnaire. DCS contacted Joe Bland Construction, L.P. regarding these two items which were subsequently submitted, reviewed by DCS, and correctly filled out to meet the requirements for the project. DCS also contacted several of Joe Bland Construction, LP's references, and documented their experience as it relates to this project. The references gave very favorable recommendations for work completed for them and/or recommended them for a project of the size and complexity of this project.


Based on the information presented, we recommend that PCDC accept the bid of Joe Bland Construction, LP with a Total Bid amount of \$2,382,550.50 for the construction of the Impact Way Extension Phase III A & B Project which includes approximately 750 linear feet of 12" water lines, 500 linear feet of 7'x4' box culvert, 160 linear feet of 10'x6' box culvert, 500 linear feet of 18"-36" storm sewer, 4 retaining wall structures, 940 linear feet of new 48'-wide asphalt roadway with sidewalks, grading, site work, and appurtenances, Emergency Access Driveway on Lot 3F to Sun Light Near Way.

Ms. Amy Madison  
March 14, 2022  
Page 2 of 2

If you have any questions, please call me at (512) 614-6171.

Sincerely,

DCS Engineering, LLC



Darren C Strozewski, P.E.  
Principal

Enclosures



3/14/22

**PCDC**  
**Impact Way Extension - Phase III A & B**  
**Bids Opened: 3/11/22 at 10:00 am**

<b>BID TABULATION</b>	<b>Joe Bland Construction, LP</b>	<b>Patin Construction</b>
Addenda Acknowledged (Y/N)	Y	Y
Bid Proposal Form (Y/N)	Y	Y
Bid Bond (Y/N)	Y	Y
Bidder's Questionnaire (Y/N)	N	N
Conflict of Interest Questionnaire (Y/N)	N	Y
Non-Collusion Certificate (Y/N)	Y	Y
State of Texas Tax Code, Chapter 151 Compliance Certificate (Y/N)	Y	Y
Compliance to Texas State Law Regarding Nonresident Bidders (Y/N)	Y	Y

<b>Bid Item</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total Amount</b>	<b>Unit Price</b>	<b>Total Amount</b>
<b>GENERAL BID ITEMS:</b>							
1	Mobilization (maximum 5% of total Bid)	1	LS	\$ 100,000.00	\$ 100,000.00	\$ 150,000.00	\$ 150,000.00

**IMPACT WAY PHASE III-A BID ITEMS**

<b>EROSION CONTROL ITEMS:</b>							
2	Clearing and Grubbing of Areas as required to complete Items within Street Right-of-Way, Utility Easements, and areas as shown on the clearing plan, Complete in Place:	8.45	AC	\$ 750.00	\$ 6,337.50	\$ 1,750.00	\$ 14,787.50
3	Off-site Disposal of Cleared and Grubbed Material in the Event of Burning Ban, Complete in Place:	4.65	AC	\$ 3,700.00	\$ 17,205.00	\$ 1,000.00	\$ 4,650.00
4	Furnish, Install, Maintain and Remove Stabilized Construction Access as shown on the Plans, Complete in Place:	70	SY	\$ 20.00	\$ 1,400.00	\$ 22.00	\$ 1,540.00
4B	Furnish, Install, Maintain and Remove/Dispose of Temporary Low Water Crossing with appurtenances, Complete in Place:	1	LS	\$ 3,200.00	\$ 3,200.00	\$ 15,000.00	\$ 15,000.00
5	Install Rock Filter Dam, Complete in Place:	155	LF	\$ 28.00	\$ 4,340.00	\$ 30.00	\$ 4,650.00
6	Pollution Prevention Implementation including Maintenance, Permitting, Inspections, and Reporting for all Pollution Prevention Measures as shown on the plans, Complete in Place:	1	LS	\$ 6,100.00	\$ 6,100.00	\$ 3,000.00	\$ 3,000.00
7	Furnish and Install Filter Fabric Fence per Plans and Specifications for project site including the relocation of existing fence. Install all filter fabric for the site prior to any other construction, Complete in Place:	3,837	LF	\$ 4.00	\$ 15,348.00	\$ 4.00	\$ 15,348.00
8	Furnish and Install Excelsior Blanket per Plans and Specifications, Complete in Place:	5,550	SY	\$ 2.00	\$ 11,100.00	\$ 2.00	\$ 11,100.00
9	Furnish and Install Curb Inlet Protection, Complete in Place:	4	EA	\$ 115.00	\$ 460.00	\$ 150.00	\$ 600.00
10	Furnish and Install Hydromulch Seeding of disturbed areas, Complete in Place:	7.55	AC	\$ 2,000.00	\$ 15,100.00	\$ 2,750.00	\$ 20,762.50
11	Furnish, Install, Maintain, and Remove tree protection, Complete in Place:	1	LS	\$ 3,865.00	\$ 3,865.00	\$ 1,000.00	\$ 1,000.00
12	Furnish, Install, Maintain, and Remove concrete washout, Complete in Place:	1	LS	\$ 650.00	\$ 650.00	\$ 1,000.00	\$ 1,000.00
<b>EARTHWORK ITEMS:</b>							
13	Cut, Place, and Compact material taken from borrow area at locations shown on the grading plan including Stripping Topsoil, Finished Grading, and reinstalling 4-inches of topsoil. Fill under proposed roadway shall use the Density Control method of Construction, Complete in Place	4,653	CY	\$ 14.00	\$ 65,142.00	\$ 35.00	\$ 162,855.00
14	Furnish and Install Concrete Pilot Channel, Complete in Place:	110	SY	\$ 85.00	\$ 9,350.00	\$ 75.00	\$ 8,250.00

**PCDC**  
**Impact Way Extension - Phase III A & B**  
**Bids Opened: 3/11/22 at 10:00 am**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount
15	Furnish and Install 12" Rock Rip-Rap, Complete in Place:	122	SY	\$ 80.00	\$ 9,760.00	\$ 50.00	\$ 6,100.00
16	Furnish and Install 9" Rock Rip-Rap, Complete in Place:	203	SY	\$ 50.00	\$ 10,150.00	\$ 45.00	\$ 9,135.00
	<b>WATER LINE ITEMS:</b>						
17	Furnish and Install 12-Inch AWWA C-900 PVC Pipe (rated at 200 psi, min.), including fittings, joint restraints, polyethylene wrap, thrust blocking, dewatering, surface restoration, disposal of excess material, and appurtenances with standard bedding and backfill, Complete in Place:	184	LF	\$ 145.00	\$ 26,680.00	\$ 125.00	\$ 23,000.00
18	Furnish and Install 12-Inch Gate Valve with Box, Complete in Place:	1	EA	\$ 4,100.00	\$ 4,100.00	\$ 7,500.00	\$ 7,500.00
19	Furnish and Install Standard City of Pflugerville Fire Hydrant, including tee, 6-Inch Gate Valve with Box, 6-Inch Lead, Thrust Blocking, and Flushing Valve, all depths, Complete in Place:	1	EA	\$ 7,245.00	\$ 7,245.00	\$ 7,500.00	\$ 7,500.00
20	Furnish and Install Trench Safety System for water line construction, Complete in Place:	184	LF	\$ 2.00	\$ 368.00	\$ 4.00	\$ 736.00
21	Cleaning, Flushing, and Disinfection, and pressure testing all waterlines including installation and removal of temporary flushing valves and piping, Complete in Place:	1	LS	\$ 4,000.00	\$ 4,000.00	\$ 3,000.00	\$ 3,000.00
22	Furnish and Install Standard City of Pflugerville 2" Blow-Off. Complete in Place:	1	EA	\$ 3,600.00	\$ 3,600.00	\$ 5,000.00	\$ 5,000.00
23	Furnish and Install 24-inch steel casing pipe (7/16" wall thickness) by open cut, not including 12" carrier pipe, with appurtenances, Complete in Place:	18	LF	\$ 270.00	\$ 4,860.00	\$ 250.00	\$ 4,500.00
24	Furnish and Install 300 psi Flowable Fill encasement.	3.4	CY	\$ 250.00	\$ 850.00	\$ 300.00	\$ 1,020.00
	<b>STORM SEWER ITEMS:</b>						
25	Furnish and Install Standard City of Pflugerville Storm Sewer Inlet, with 5' Extension, Complete in Place:	2	EA	\$ 8,100.00	\$ 16,200.00	\$ 7,500.00	\$ 15,000.00
26	Furnish and Install 18-Inch RCP, C-76 Class III Storm Sewer Inlet Leads with bedding and backfill, Complete in Place:	41	LF	\$ 88.00	\$ 3,608.00	\$ 75.00	\$ 3,075.00
27	Furnish and Install 7' x 4' RCB Storm Sewer ASTM C-789 and ASTM C-850 with Bedding and Backfill, Complete in Place:	524	LF	\$ 580.00	\$ 303,920.00	\$ 550.00	\$ 288,200.00
28	Furnish and Install Standard Storm Sewer Manhole for proposed 7'x4' RCB, all depths, Complete in Place:	1	EA	\$ 2,400.00	\$ 2,400.00	\$ 7,500.00	\$ 7,500.00
29	Furnish and Install Wing Wall Outlet Structure with energy dissipation for 7' x 4' RCB, Complete in Place:	1	LS	\$ 35,000.00	\$ 35,000.00	\$ 15,000.00	\$ 15,000.00
30	Furnish and Install Trench Safety System for Storm Sewer Construction, Complete in Place:	565	LF	\$ 2.00	\$ 1,130.00	\$ 4.00	\$ 2,260.00
	<b>PAVING ITEMS:</b>						
31	Asphalt Pavement Road: Furnish Lime for 8" Subgrade Stabilization at 6%	77	TON	\$ 380.00	\$ 29,260.00	\$ 225.00	\$ 17,325.00
32	Asphalt Pavement Road: Prepare and Stabilize 8" Subgrade, Including all Equipment and Labor, Complete in Place:	3,577	SY	\$ 2.00	\$ 7,154.00	\$ 10.00	\$ 35,770.00
33	Furnish and Install 18-Inch Flexible Base Type A, Grade 1 with Geogrid, Complete in Place:	3,577	SY	\$ 25.00	\$ 89,425.00	\$ 28.00	\$ 100,156.00
34	Asphalt Pavement Road: Furnish and Install Prime Coat, Complete in Place:	742	GAL	\$ 6.50	\$ 4,823.00	\$ 10.00	\$ 7,420.00
35	Asphalt Pavement Road: Furnish and Install 2-inch HMA, Type B per	3,204	SY	\$ 22.50	\$ 72,090.00	\$ 17.00	\$ 54,468.00
36	Asphalt Pavement Road: Furnish and Install 2-Inch HMA, Type C per TXDOT Specification Item 340, Complete in Place:	3,204	SY	\$ 24.00	\$ 76,896.00	\$ 20.00	\$ 64,080.00
37	Furnish and Install 6-Inch Concrete Curb, including Reinforcing Steel, Concrete, Labor and Appurtenances, Complete in Place:	1,231	LF	\$ 15.00	\$ 18,465.00	\$ 15.00	\$ 18,465.00
38	Furnish and Install Pavement Marking, Thermoplastic, Reflective, White, 4" BRK, 100 mil, Complete in Place:	1,120	LF	\$ 1.50	\$ 1,680.00	\$ 7.00	\$ 7,840.00

**PCDC**  
**Impact Way Extension - Phase III A & B**  
**Bids Opened: 3/11/22 at 10:00 am**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount
39	Furnish and Install Pavement Marking, Thermoplastic, Reflective, Yellow, 4" SLD, 100 mil, Complete in Place:	1,120	LF	\$ 1.50	\$ 1,680.00	\$ 7.00	\$ 7,840.00
40	Furnish, Install, and Maintain Traffic Control Devices on Impact Way and Sun Light Near Way with appurtenances, in accordance with Texas Manual on Uniform Traffic Control Devices (Latest Edition); Complete in Place:	1	LS	\$ 3,000.00	\$ 3,000.00	\$ 8,500.00	\$ 8,500.00
41	Adjust grade of existing sanitary sewer manholes. Complete in place:	2	EA	\$ 400.00	\$ 800.00	\$ 500.00	\$ 1,000.00
	<b>SIDEWALK ITEMS:</b>						
42	Furnish and Install 6-Foot Concrete Sidewalk, Complete in Place:	735	SY	\$ 55.00	\$ 40,425.00	\$ 30.00	\$ 22,050.00
43	Construct wheel chair ramps (all types) per plans and specifications	4	EA	\$ 1,450.00	\$ 5,800.00	\$ 3,000.00	\$ 12,000.00
	<b>EMERGENCY ACCESS DRIVEWAY:</b>						
44	Furnish and Install 110' Long, 26' Wide Grasscrete Driveway with grading,	1	LS	\$ 70,000.00	\$ 70,000.00	\$ 60,000.00	\$ 60,000.00
45	Furnish and Install Emergency Access Gate including Knox Padlock	2	EA	\$ 5,000.00	\$ 10,000.00	\$ 6,500.00	\$ 13,000.00
	<b>GENERAL:</b>						
46	Furnish and Install Traffic and Street Signs including all Signage, Material	2	EA	\$ 400.00	\$ 800.00	\$ 500.00	\$ 1,000.00
47	Furnish and Install Project Sign including all Material and Labor, Complete in Place:	1	EA	\$ 3,220.00	\$ 3,220.00	\$ 500.00	\$ 500.00
48	Furnish and Install Standard City of Pflugerville Type III Barricade, Complete in Place:	2	EA	\$ 2,025.00	\$ 4,050.00	\$ 3,000.00	\$ 6,000.00
49	Furnish and Install 6" Diameter Pipe Bollard, Complete in Place:	11	EA	\$ 1,150.00	\$ 12,650.00	\$ 1,000.00	\$ 11,000.00
50	Furnish and Install Concrete street light foundation including all Material and Labor, Complete in Place:	3	EA	\$ 2,950.00	\$ 8,850.00	\$ 2,500.00	\$ 7,500.00
51	Demolition shown on 01C-01. Proposed/Restored Items called out on this Drawing (including Filling, Sidewalks, Ramps, Curbs, Sleeves, and Valves) are included in other bid item quantities, Complete in Place:	1	LS	\$ 15,000.00	\$ 15,000.00	\$ 10,000.00	\$ 10,000.00
52	Furnish, Install, and maintain watering and/or temporary irrigation system until revegetation is established per City of Pflugerville specifications, Complete in Place:	1	LS	\$ 9,165.00	\$ 9,165.00	\$ 2,500.00	\$ 2,500.00
	<b>IMPACT WAY PHASE III-B BID ITEMS:</b>						
	<b>EROSION CONTROL ITEMS:</b>						
53	Clearing and Grubbing of Areas as required to complete Items within Street Right-of-Way, Utility Easements, and areas as shown on the clearing plan, Complete in Place:	1.68	AC	\$ 4,325.00	\$ 7,266.00	\$ 1,750.00	\$ 2,940.00
54	Furnish, Install, Maintain and Remove Stabilized Construction Access as shown on the Plans, Complete in Place:	70	SY	\$ 20.00	\$ 1,400.00	\$ 22.00	\$ 1,540.00
55	Install Rock Filter Dam, Complete in Place:	105	LF	\$ 28.00	\$ 2,940.00	\$ 30.00	\$ 3,150.00
56	Pollution Prevention Implementation including Maintenance, Permitting, Inspections, and Reporting for all Pollution Prevention Measures as shown on the plans, Complete in Place:	1	LS	\$ 3,800.00	\$ 3,800.00	\$ 3,000.00	\$ 3,000.00
57	Furnish and Install Filter Fabric Fence per Plans and Specifications for project site including the relocation of existing fence. Install all filter fabric for the site prior to any other construction, Complete in Place:	2,967	LF	\$ 4.00	\$ 11,868.00	\$ 4.00	\$ 11,868.00
58	Furnish and Install Excelsior Blanket per Plans and Specifications, Complete in Place:	2,317	SY	\$ 3.00	\$ 6,951.00	\$ 2.00	\$ 4,634.00
59	Furnish and Install Curb Inlet Protection, Complete in Place:	4	EA	\$ 115.00	\$ 460.00	\$ 150.00	\$ 600.00
60	Furnish and Install Hydromulch Seeding of disturbed areas, Complete in Place:	1.11	AC	\$ 3,100.00	\$ 3,441.00	\$ 2,750.00	\$ 3,052.50
61	Furnish, Install, Maintain, and Remove tree protection, Complete in Place:	1	LS	\$ 1,935.00	\$ 1,935.00	\$ 1,000.00	\$ 1,000.00

**PCDC**  
**Impact Way Extension - Phase III A & B**  
**Bids Opened: 3/11/22 at 10:00 am**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount
62	Furnish, Install, Maintain, and Remove concrete washout, Complete in Place:	1	LS	\$ 650.00	\$ 650.00	\$ 1,000.00	\$ 1,000.00
	<b>EARTHWORK ITEMS:</b>						
63	Cut, Place, and Compact material taken from borrow area at locations shown on the grading plan including Stripping Topsoil, Finished Grading, and reinstalling 4-inches of topsoil. Fill under proposed roadway shall use the Density Control method of Construction, Complete in Place	2,327	CY	\$ 14.00	\$ 32,578.00	\$ 35.00	\$ 81,445.00
64	Furnish and Install 1'-6" Rock Rip-Rap, Complete in Place:	1,508	SY	\$ 60.00	\$ 90,480.00	\$ 65.00	\$ 98,020.00
	<b>WATER LINE ITEMS:</b>						
65	Furnish and Install 12-Inch AWWA C-900 PVC Pipe (rated at 200 psi, min.), including fittings, joint restraints, polyethylene wrap, thrust blocking, dewatering, surface restoration, disposal of excess material, and appurtenances with standard bedding and backfill, Complete in Place:	490	LF	\$ 160.00	\$ 78,400.00	\$ 125.00	\$ 61,250.00
66	Furnish and Install 12-Inch Gate Valve with Box, Complete in Place:	3	EA	\$ 4,100.00	\$ 12,300.00	\$ 7,500.00	\$ 22,500.00
67	Furnish and Install Standard City of Pflugerville Fire Hydrant, including tee, 6-Inch Gate Valve with Box, 6-Inch Lead, Thrust Blocking, and Flushing Valve, all depths, Complete in Place:	1	EA	\$ 7,245.00	\$ 7,245.00	\$ 7,500.00	\$ 7,500.00
68	Furnish and Install Trench Safety System for water line construction, Complete in Place:	490	LF	\$ 2.00	\$ 980.00	\$ 4.00	\$ 1,960.00
69	Cleaning, Flushing, and Disinfection, and pressure testing all waterlines including installation and removal of temporary flushing valves and piping, Complete in Place:	1	LS	\$ 4,000.00	\$ 4,000.00	\$ 3,000.00	\$ 3,000.00
70	Furnish and Install Standard City of Pflugerville 2" Blow-Off. Complete in Place:	2	EA	\$ 3,600.00	\$ 7,200.00	\$ 5,000.00	\$ 10,000.00
71	Furnish and Install 24-inch steel casing pipe (7/16" wall thickness) by open cut, not including 12" carrier pipe, with appurtenances, Complete in Place:	70	LF	\$ 260.00	\$ 18,200.00	\$ 250.00	\$ 17,500.00
	<b>STORM SEWER ITEMS:</b>						
72	Furnish and Install Standard City of Pflugerville Storm Sewer Inlet, with 5' Extension, Complete in Place:	2	EA	\$ 8,115.00	\$ 16,230.00	\$ 6,500.00	\$ 13,000.00
73	Furnish and Install 24-Inch RCP, C-76 Class III Storm Sewer Inlet Leads with bedding and backfill, Complete in Place:	133	LF	\$ 98.00	\$ 13,034.00	\$ 115.00	\$ 15,295.00
74	Furnish and Install Standard Storm Sewer Manhole, all depths, Complete in Place:	1	EA	\$ 5,140.00	\$ 5,140.00	\$ 6,500.00	\$ 6,500.00
75	Furnish and Install Trench Safety System for Storm Sewer Construction, Complete in Place:	133	LF	\$ 2.00	\$ 266.00	\$ 4.00	\$ 532.00
	<b>PAVING ITEMS:</b>						
76	Asphalt Pavement Road: Furnish Lime for 8" Subgrade Stabilization at 6% by weight, Including all Material and Labor, Complete in Place:	54	TON	\$ 380.00	\$ 20,520.00	\$ 225.00	\$ 12,150.00
77	Asphalt Pavement Road: Prepare and Stabilize 8" Subgrade, Including all Equipment and Labor, Complete in Place:	2,506	SY	\$ 2.00	\$ 5,012.00	\$ 10.00	\$ 25,060.00
78	Furnish and Install 18-Inch Flexible Base Type A, Grade 1 with Geogrid, Complete in Place:	2,506	SY	\$ 25.00	\$ 62,650.00	\$ 28.00	\$ 70,168.00
79	Asphalt Pavement Road: Furnish and Install Prime Coat, Complete in Place:	522	GAL	\$ 6.50	\$ 3,393.00	\$ 10.00	\$ 5,220.00
80	Asphalt Pavement Road: Furnish and Install 2-inch HMA, Type B per TXDOT Specification Item 340, Complete in Place:	2,252	SY	\$ 22.50	\$ 50,670.00	\$ 17.00	\$ 38,284.00
81	Asphalt Pavement Road: Furnish and Install 2-Inch HMA, Type C per TXDOT Specification Item 340, Complete in Place:	2,252	SY	\$ 24.00	\$ 54,048.00	\$ 20.00	\$ 45,040.00

**PCDC**  
**Impact Way Extension - Phase III A & B**  
**Bids Opened: 3/11/22 at 10:00 am**

Bid Item	Description	Quantity	Unit	Unit Price	Total Amount	Unit Price	Total Amount
82	Furnish and Install 6-Inch Concrete Curb, including Reinforcing Steel, Concrete, Labor and Appurtenances, Complete in Place:	790	LF	\$ 15.00	\$ 11,850.00	\$ 15.00	\$ 11,850.00
83	Furnish and Install Pavement Marking, Thermoplastic, Reflective, White, 4" BRK, 100 mil, Complete in Place:	762	LF	\$ 1.50	\$ 1,143.00	\$ 7.00	\$ 5,334.00
84	Furnish and Install Pavement Marking, Thermoplastic, Reflective, Yellow, 4" SLD, 100 mil, Complete in Place:	762	LF	\$ 1.50	\$ 1,143.00	\$ 7.00	\$ 5,334.00
85	Furnish, Install, and Maintain Traffic Control Devices on Impact Way and Sun Light Near Way with appurtenances, in accordance with Texas Manual on Uniform Traffic Control Devices (Latest Edition); Complete in Place:	1	LS	\$ 4,000.00	\$ 4,000.00	\$ 8,500.00	\$ 8,500.00
<b>CULVERT BRIDGE ITEMS:</b>							
86	Furnish and Install Culvert bridge as shown on sheet 02S-03 including 3-36" RCP Culverts, Concrete Retaining Wall Structures including Footing for 3-36" RCP Culverts, all formwork, reinforcing steel, and appurtenances, Complete in Place:	1	LS	\$ 115,256.00	\$ 115,256.00	\$ 380,000.00	\$ 380,000.00
87	Furnish and Install Culvert bridge as shown on sheet 02S-02 including 2-10'x6' RCB Culverts, Concrete Retaining Wall Structures including Footing for 2-10'x6' RCB Culvert, all formwork, reinforcing steel, and appurtenances, Complete in Place:	1	LS	\$ 315,000.00	\$ 315,000.00	\$ 720,000.00	\$ 720,000.00
<b>SIDEWALK ITEMS:</b>							
88	Furnish and Install 6-Foot Concrete Sidewalk, Complete in Place:	459	SY	\$ 55.00	\$ 25,245.00	\$ 25.00	\$ 11,475.00
89	Construct wheel chair ramps (all types) per plans and specifications including any restoration and tie-ins to existing sidewalks or trails, Complete in Place:	2	EA	\$ 1,450.00	\$ 2,900.00	\$ 2,500.00	\$ 5,000.00
<b>GENERAL:</b>							
90	Furnish and Install Traffic and Street Signs including all Signage, Material and Labor, Complete in Place per sign pole:	1	EA	\$ 400.00	\$ 400.00	\$ 500.00	\$ 500.00
91	Furnish and Install Project Sign including all Material and Labor, Complete in Place:	1	EA	\$ 1,930.00	\$ 1,930.00	\$ 500.00	\$ 500.00
92	Furnish and Install Standard City of Pflugerville Type III Barricade, Complete in Place:	2	EA	\$ 2,025.00	\$ 4,050.00	\$ 3,000.00	\$ 6,000.00
93	Furnish and Install 6" Diameter Pipe Bollard, Complete in Place:	9	EA	\$ 1,150.00	\$ 10,350.00	\$ 1,000.00	\$ 9,000.00
94	Furnish and Install Concrete street light foundation including all Material and Labor, Complete in Place:	1	EA	\$ 3,500.00	\$ 3,500.00	\$ 2,500.00	\$ 2,500.00
95	Demolition shown on 01C-01. Proposed/Restored Items called out on this Drawing (including Filling, Sidewalks, Ramps, Curbs, Sleeves, and Valves) are included in other bid item quantities, Complete in Place:	1	LS	\$ 15,000.00	\$ 15,000.00	\$ 10,000.00	\$ 10,000.00
96	Furnish, Install, and maintain watering and/or temporary irrigation system until revegetation is established per City of Pflugerville specifications, Complete in Place:	1	LS	\$ 9,000.00	\$ 9,000.00	\$ 2,500.00	\$ 2,500.00
97	Furnish and Install Metal Beam Guard Fence per Plans, including all Materials, Labor and Appurtenances, Complete in Place:	285	LF	\$ 185.00	\$ 52,725.00	\$ 150.00	\$ 42,750.00
98	Furnish and Install TxDOT Combination (Pedestrian/Traffic) Rail per Plans, including all Materials, Labor and Appurtenances, Complete in Place:	370	LF	\$ 290.00	\$ 107,300.00	\$ 250.00	\$ 92,500.00
<b>TOTAL IMPACT WAY PHASE III A &amp; B BID AMOUNT</b>					<b>\$ 2,382,550.50</b>		<b>\$ 3,162,434.50</b>