

J.F. FONTAINE & ASSOCIATES, INC.

CONSULTING ENGINEERS

P.O.	Box	4187
Telephone (903) 729-6005		
Palestine,	Texas	75802
Fax (903) 729-7310		

MANVILLE WATER SUPPLY CORPORATION
PFLUGERVILLE PARKWAY 12" WATERLINE

DATE: AUGUST 28, 2019

NAME OF BIDDERS	AMOUNT BID
NELSON LEWIS, INC.	\$1,024,013.00*
HERSCHAP BACKHOE	\$1,483,385.00
WHITNEY UNDERGROUND	\$2,197,700.00

ITEM NO.	DESCRIPTION	NELSON LEWIS	HERSCHAP	WHITNEY
1.	Mobilization for all Work Covered	20,000.00	30,000.00	100,000.00
2.	Furnish 12" C900 DR18-235 Pipe equipment material, labor	50.00	90.00	134.00
3.	Furnish Bedding for 12" C900 DR18-235 Pipe equipment material, labor	9.00	15.00	10.00
4.	Furnish equipment, material, labor to Remove/Dispose of 10" PVC Pipe	3.00	30.00	20.00
5.	Furnish 10" C900 DR18-235 Pipe equipment material, labor	75.00	80.00	110.00
6.	Furnish 8" C900 DR18-235 Pipe equipment material, labor	95.00	50.00	100.00
7.	Furnish 20" Steel Pipe Encasement with 12" Eagle Lock 900 PVC Carrier Pipe	630.00	750.00	700.00
8.	Furnish 12" PVC Pipe equipment, material labor to bore only	230.00	160.00	300.00
9.	Furnish 12" Gate Valve equipment, material equipment to install	2,800.00	3,000.00	5,000.00
10.	Furnish 10" Gate Valve equipment, material equipment to install	2,300.00	2,000.00	4,000.00
11.	Furnish 6" Gate Valve equipment, material equipment to install	1,200.00	1,000.00	2,000.00
12.	Furnish equipment, material, equipment to install 12" GV on existing 12" connection	3,500.00	5,200.00	6,000.00
13.	Furnish equipment, material, equipment to install 8" GV on existing 8" Gate Valve	2,000.00	3,500.00	4,000.00
14.	Furnish 2" Flush Valve equipment, material equipment to install	1,168.00	1,500.00	2,500.00
15.	Furnish 2" Air Release Valve equipment, labor to install	3,500.00	4,000.00	6,000.00

16.	Furnish material, labor, equipment to to install 11" to 16" Wet Connection	8,000.00	10,000.00	12,000.00
-----	---	----------	-----------	-----------

ITEM NO.	DESCRIPTION	NELSON LEWIS	HERSCHAP	WHITNEY
17.	Furnish material, labor, equipment to to install 12" to 12" Wet Connection	5,000.00	7,000.00	5,000.00
18.	Furnish material, labor, equipment to to install 12" to 6" Wet Connection	2,500.00	5,500.00	4,000.00
19.	Furnish material, labor, equipment to to install 10" to 10" Wet tie-in	2,500.00	6,000.00	5,000.00
20.	Furnish material, labor, equipment to cut/cap existing 10" line	500.00	1,200.00	3,000.00
21.	Furnish material, labor, equipment water required for hydromulch re-vegetation and restoration disturbed areas	1.00	.60	6.00
22.	Furnish material, labor, equipment water required for sodding re-vegetation and restoration disturbed areas	5.00	35.00	30.00
23.	Furnish material, labor, equipment to remove, dispose & reconstruct concrete hike & bike path	77.00	110.00	140.00
24.	Furnish material, labor, equipment to remove, store & reconstruct existing fencing to original condition	6.00	3.00	50.00
25.	Furnish material, labor, equipment to curb inlet protection	400.00	200.00	3,000.00
26.	Furnish material, labor, equipment to install Rock Berm	25.00	30.00	200.00
27.	Furnish material, labor, equipment install Site Fence	3.50	3.00	6.00
28.	Furnish material, labor, equipment to install Line Markers	200.00	40.00	100.00
29.	Furnish material, labor, equipment install Trench Shoring	2.00	2.00	5.00
30.	Furnish 12" C900 Ball Joint Restraint and all equipment, material, labor to instal	350.00	225.00	5,000.00
31.	Furnish 10" C900 Ball Joint Restraint and all equipment, material, labor to instal	325.00	200.00	5,000.00
32.	Furnish 16" C900 Ball Joint Restraint and all equipment, material, labor to instal	1,200.00	1,000.00	10,000.00
33.	Furnish material, labor, equipment to cut remove & repair concrete apron	15.00	10.00	50.00
34.	Furnish material, labor, equipment, to install 2" flush valve on 12" line field located	2,100.00	1,500.00	3,000.00

* CONTRACT PENDING