



## THE RIDGE AT BLACKHAWK PHASE 1 PRELIMINARY PLAN ONLY-NOT FOR RECORDATION










MATCH LINE - SEE THIS SHEET

NOTES:

1. THERE ARE NO EXISTING STRUCTURES WITHIN PROJECT BOUNDARY.
2. EXISTING GAS LINE EASEMENTS EXIST ON AND AROUND THIS PRJOECT.
3. THERE WILL BE NO DEMOLITION ON THIS SITE AS THERE ARE NO EXISTING STRUCTURES.



## **LEGEND**

P635 = PROPOSED MJR CONTOUR  
P632 = PROPOSED MNR CONTOUR

— — — — 620 — — — = EXISTING MJR CONTOUR

..... 614 .. = EXISTING MNR CONTOUR

A topographic map segment showing a contour line labeled 'Z'. The map includes a scale bar at the bottom with markings for 200', 300', and 400'.


**PROJECT: THE RIDGE AT BLACKHAWK PHASE 1**


**SHEET: EXISTING CONDITIONS & PROPOSED GRADING PLAN SHEET**

A circular seal for a Texas registered professional engineer. It features a five-pointed star in the center, surrounded by the words "STATE OF TEXAS" at the top and "REGISTERED PROFESSIONAL ENGINEER" at the bottom. The name "J. KEITH COLLINS" is written across the center, and the number "80579" is below it. The entire seal is enclosed in a decorative border.


DATE:	JAN. 2019
DRAWN:	
CHECKED:	JKC
FILE:	2500
SCALE	1" = 100'

SHEET  
04





MACH LINE - SEE THIS SHEET



## **LEGEND**

---

- = STORM SEWER MANHOLE
  - = CURB INLET
  - = WASTEWATER MANHOLE
  - = WATER VALVE
  - = FIRE HYDRANT
  - = STREET LIGHT

SINGLE WASTEWATER SERVICE

DOUBLE WASTEWATER SERVICE

SINGLE WATER SERVICE

DOUBLE WATER SERVICE

 = 12" WATER LINE

 = 8" WATER LINE

 = WW LINE

SCALE: 1"=100'

A scale bar at the bottom of the page features a series of vertical tick marks. Above these marks, horizontal lines extend to labels: '100'' on the left, '200'' in the center, '300'' on the right, and '400'' further to the right. The entire scale is labeled 'SCALE. 1 - 100' at the top center.

RANDALL  
JONES &  
ASSOCIATES  
ENGINEERING  
INC  
#9784

2900 JAZZ STREET  
ROUND ROCK, TX 78664  
(512) 836-4793

PROJECT: THE BIDGE AT BLACKHAWK PHASE 1

SHEET:

A circular seal for a Texas Professional Engineer. The outer ring contains the words "STATE OF TEXAS" at the top and "PROFESSIONAL ENGINEER" at the bottom, separated by a dotted line. The inner circle features a five-pointed star in the center, surrounded by the name "J. KEITH COLLINS" and the registration number "80579".

DATE:	JAN. 2019
DRAWN:	
CHECKED:	JKC
FILE:	2500
SCALE	1"=100'

SHEET  
05


## NOTES:

1) ALL STREET LIGHT LUMINARIES TO BE DOWNCAST AND FULL CUT-OFF TYPE. LUMINAIRE TO BE LED. DROP DOWN LENS IS PROHIBITED. STREETLIGHTS TO BE INSTALLED AND OPERATIONAL PRIOR TO CONSTRUCTION ACCEPTANCE.

STREET LIGHTS AT PROPERTY LINES SHALL BE LOCATED 3.0' FROM EXTENSIONS OF PROPERTY LINE ALONG CURB LINE. SEE DETAIL BELOW.



卷之三



LOT 7

10' NATURAL GAS PIPELINE  
EASEMENT TO SIENERGY, L.P.  
DOC. NO. 2018055778 OPRTC

LOT 8


A diagram consisting of three line segments. A vertical line segment is positioned on the left side of the frame. A horizontal line segment is located on the right side. A diagonal line segment connects the bottom of the vertical line to the middle of the horizontal line.

				20
				21
				BLOCK A
	24			22
			23	

SPE  
DRIV

73936.370  
4291.470

RTNERSHIP - 1.57 ACRES - DOC. NO. 2016120723 OPRTC  
BOARD OF TRUSTEES OF THE PFLUGERVILLE  
INDEPENDENT SCHOOL DISTRICT  
REMAINDER OF 40.00 ACRES  
DOC. NO. 2014054501 ODPBC



# **LEGEND**

1. Pipe material for water mains shall be PVC DR14 (AWWA C-900, min class 305), or Ductile Iron (AWWA C-100, min 150). Water services (2" or less) shall be polyethylene tubing (200 psi, DR9).
  2. Pipe material for pressure wastewater mains shall be PVC (AWWA C-900, min. class 150) or Ductile Iron (AWWA C-100, min. class 150). Pipe material for gravity wastewater mains shall be PVC (SDR 26). SDR-35 wastewater is not allowed in the right of way or public easement.
  3. Temporary blow-off valves will be installed at the end of all temporary dead-end water mains.


*SCALE: 1"=100'*

 = STORM SEWER MANHOLE  
 = CURB INLET  
 = WASTEWATER MANHOLE  
 = WATER VALVE  
 = FIRE HYDRANT  
 = STREET LIGHT  
  
 = SINGLE WASTEWATER SERVICE  
 = DOUBLE WASTEWATER SERVICE  
  
 = SINGLE WATER SERVICE  
 = DOUBLE WATER SERVICE  
  
 = 12" WATER LINE  
 = 8" WATER LINE  
 = WW LINE

RANDALL  
JONES &  
ASSOCIATES  
ENGINEERING  
INC.  
#9784


900 JAZZ STREET  
OUND ROCK, TX 78664  
(12) 836-4793

**SHEET: WATER & WASTEWATER PLAN ( SHEET 1 OF 2)**




TE: JAN. 2019  
AWN:  
ECKED: JKC  
E: 2500  
ALE 1"=100'

HEET




MATCH LINE - SEE SHEET 06



Notes:

1. Pipe material for water mains shall be PVC DR14 (AWWA C-900, min class 305), or Ductile Iron (AWWA C-100, min 150). Water services (2" or less) shall be polyethylene tubing (200 psi, DR9).
2. Pipe material for pressure wastewater mains shall be PVC (AWWA C-900, min. class 150) or Ductile Iron (AWWA C-100, min. class 150). Pipe material for gravity wastewater mains shall be PVC (SDR 26). SDR-35 wastewater is not allowed in the right of way or public easement.
3. Temporary blow-off valves will be installed at the end of all temporary dead-end water mains.


SCALE: 1"=100'



LEGEND	BY
(○) = STORM SEWER MANHOLE	
(■) = CURB INLET	
(◎) = WASTEWATER MANHOLE	
(W) = WATER VALVE	
(H) = FIRE HYDRANT	
(▲) = STREET LIGHT	
(○) = SINGLE WASTEWATER SERVICE	
(●) = DOUBLE WASTEWATER SERVICE	
(□) = SINGLE WATER SERVICE	
(■) = DOUBLE WATER SERVICE	
— 12" W = 12" WATER LINE	
- - - 8" W = 8" WATER LINE	
— - - - WW LINE	


RANDALL JONES & ASSOCIATES ENGINEERING INC.  
#9784  
2900 JAZZ STREET  
ROUND ROCK, TX 78664  
(512) 836-4793

PROJECT: THE RIDGE AT BLACKHAWK PHASE 1  
SHEET: WATER & WASTEWATER PLAN (SHEET 2 OF 2)



DATE: JAN. 2019  
DRAWN:  
CHECKED: JKC  
FILE: 2500  
SCALE: 1"=100'

SHEET 07



## LEGEND

- = REMOVE TREE
- = SAVE TREE


SCALE: 1"=100'  
0 100' 200' 300' 400'

NO.	DATE	DESCRIPTION	BY

RANDALL JONES & ASSOCIATES ENGINEERING INC. #9784  
2900 JAZZ STREET ROUND ROCK, TX 78664 (512) 836-4793

PROJECT: THE RIDGE AT BLACKHAWK PHASE 1

SHEET: TREE SURVEY



DATE: JAN. 2019  
DRAWN:  
CHECKED: JK  
FILE: 2500  
SCALE 1"=100'

SHEET 08

### 2.3.2. Tree Protection Notes:

- All trees not located within the limits of construction and outside of disturbed areas shall be preserved.
- All trees shown on this plan to be retained shall be protected during construction with fencing.
- Tree protection fences shall be erected according to city standards for tree protection, including types of fencing and signage.
- Tree protection fences shall be installed prior to the commencement of any site preparation work (clearing, grubbing, or grading) and shall be maintained throughout all phases of the construction project.
- Erosion and sedimentation control barriers shall be installed or maintained in a manner which does not result in trenching or soil build-up within tree CRZ's or driplines.
- Tree protection fences shall completely surround the tree or clusters of trees and be placed at the outermost limits of the tree branches (dripline) or CRZ, whichever is greater; and shall be maintained throughout the construction project in order to prevent the following:
  - Soil compaction in root zone area resulting from vehicular traffic or storage of equipment or material.
  - Root zone disturbances due to grade changes (greater than 6 inches cut or fill) or trenching not reviewed and authorized by the City Arborist or Administrator.
  - Wounds to exposed roots, trunk, or limbs by mechanical equipment
  - Other activities detrimental to trees, such as chemical storage, concrete truck cleaning and fires.
- Exceptions to installing tree fences at the tree driplines or CRZ, whichever is greater, may be permitted in the following cases:
  - Where there is to be an approved grade change, impermeable paving surface, or tree well.
  - Where permeable paving is to be installed, erect the fence at the outer limits of the permeable paving area.
  - Where trees are close to proposed buildings, erect the fence no closer than 6 feet to the build-line.
  - Where there are severe space constraints due to tract size, or other special requirements, contact the City Arborist to discuss alternatives.
- Where any of the above exceptions result in a fence that is closer than 5 feet to a tree trunk, protect the trunk with strapped-on planking to a height of 8 feet (or to the limits of lower branching) in addition to the reduced fencing provided.
- Where any of the above exceptions result in areas of unprotected root zones under the dripline or CRZ, whichever is greater, those areas should be covered with 6 inches of organic mulch to minimize soil compaction.
- Where any of the above exceptions result in damage to the fine, water absorbing roots, supplemental watering shall be required:
  - Trees shall be watered once every two weeks during periods of hot, dry weather.
  - Tree crowns are to be sprayed with water periodically to reduce dust accumulation on leaves.
  - A signed watering contract shall be required.
- Prior to excavation or grade cutting within tree driplines, a clean cut shall be made between the disturbed and undisturbed root zones with a rock saw or similar equipment to minimize damage to remaining roots.
- All grading within protected root zone areas shall be done by hand or with small equipment to minimize root damage. Prior to grading, relocate protective fencing to 2 feet behind the grade change area.
- Any roots exposed by construction activity shall be pruned flush with the soil. Backfill root areas with good quality top soil. If exposed root areas are not backfilled within 2 days, cover them with organic material in a manner which reduces soil temperature and minimizes water loss due to evaporation.
- When installing concrete adjacent to the root zone of a tree, use a plastic vapor barrier behind the concrete to prohibit leaching of lime into the root zone.
- Any trenching shall be as far from existing tree trunks as possible. Trench lines shall not run within the CRZ. Boring, tunneling or other techniques may be approved by the City Arborist or Administrator if there is no alternative available.
- No landscape topsoil dressing greater than four (4) inches shall be permitted within the dripline or CRZ, whichever is greater, of trees. No topsoil is permitted on root flares or within 6 inches of tree trunks.
- Pruning to provide clearance for structures, vehicular traffic and construction equipment shall take place before construction begins. All pruning must be done according to City standards and as outlined in literature provided by the International Society of Arboriculture (ISA pruning techniques).
- All oak tree cuts, intentional or unintentional, shall be painted immediately (within 10 minutes). Tree paint must be kept on site at all times. All pruning or cutting tools must be sterilized between trees to prevent the spread of disease.
- Trees approved for removal shall be removed in a manner which does not impact trees to be preserved. Refer to the City of Pflugerville Tree Technical Manual for appropriate removal methods.
- Deviations from the above notes may be considered ordinance violations if there is substantial noncompliance or if a tree sustains damage as a result.

larger of the tree(s) to be saved throughout the life of the project, or until final improvement work within the area is required, typically near the end of the project.

Parking Areas: If the fencing must be located on paving or sidewalk that will not be demolished, the posts may be supported by an appropriate grade level concrete base.


#### 2. Type II Tree Protection

For trees situated within a narrow planting strip, only the planting strip shall be fenced. If the planting strip is too narrow to accommodate fencing in order to keep the sidewalk and street open for public use, protective fencing near buildings, partial fencing may be necessary. See illustrations 2-4 and 2-5 for examples and specifications for partial wood and chain link fencing.

#### 3. Type III Tree Protection

Trees situated in a tree well or sidewall planter pit, or where construction will result in five (5) feet of a trunk, shall have the trunk protected with strapped-on planking to a height of eight (8) feet or to the limits of lower branches. During installation of the wood slats, caution shall be used to avoid damaging any bark or branches. Major scaffold limits may also need protection as directed by the City Arborist.


Illustration 2-6: Example of bark protection—done when CRZ is less than an 8 foot diameter, upon approval by the City Arborist.



d. Duration: Tree fencing shall be installed before demolition, grading, or construction begins and remain in place until the certificate of occupancy has been granted. Removal of the fence during construction must be approved by the City Arborist. Fence removal without the approval of the City Arborist or Administrator will result in a stop work order.

e. Warning sign: A warning sign shall be prominently displayed on each fence. The sign shall be a minimum of 18 x 24 inches and clearly state: WARNING - Critical Root Zone - Encroachment may result in permanent tree damage, resulting in tree replacement.

NO.	DATE	DESCRIPTION	BY



PROJECT: THE RIDGE AT BLACKHAWK, PHASE 1  
SHEET: PRELIMINARY DRAINAGE PLAN  
(SHEET 1 OF 2)





DATE: JAN. 2019  
DRAWN: MAS/EK  
CHECKED: JKJC  
FILE: 2500  
SCALE: 1"=100'

SHEET  
09



## LEGEND

- P635 = PROPOSED MJR CONTOUR
- P632 = PROPOSED MNR CONTOUR
- 620 = EXISTING MJR CONTOUR
- 614 = EXISTING MNR CONTOUR
- DRainage Basin Number  
Drainage Basin Acreage
- HP = HIGH POINT
- LP = LOW POINT
- DIRECTION OF FLOW ARROWS
- DRAINAGE BASIN BOUNDARY


REFER TO MOODY ENGINEERING  
DRAINAGE REPORT THE RIDGE AT  
BLACKHAWK, PHASE 1 DATED OCT.  
2018 (AMENDED JULY 2018) FOR  
EXISTING DRAINAGE CONDITIONS.



MATCH LINE - SEE SHEET 9



PROJECT: THE RIDGE AT BLACKHAWK, PHASE 1  
SHEET: PRELIMINARY DRAINAGE PLAN  
(SHEET 2 OF 2)



DATE: JAN. 2019  
DRAWN: MAS/EK  
CHECKED: JKC  
FILE: 2500  
SCALE 1"=100'

SHEET 10

Drainage Sub-Basin #	Area Size (ac)	Sheet Flow Over Land Surfaces		Concentrated Flow Over Land Surfaces		Concentrated Flow Street		Concentrated Flow Channels		Manning's n		Time of Concentration (min)	Intensity, I inches/hour			Impervious Cover %	Composite "C"			Total Runoff (cfs)			Drainage Sub-Basin #	REMARKS
		Length	Slope	Length	Slope	Length	Slope	Velocity	Sheet	SCF Unpaved	SCF Paved		(10 Yr)	(25 Yr)	(100 Yr)		(10 Yr)	(25 Yr)	(100 Yr)	(10 Yr)	(25 Yr)	(100 Yr)		
1	0.84	85	1.4%	105	1.1%	163	0.7%	0.15	0.15	0.015	12	6.59	7.85	10.11	33%	0.47	0.52	0.59	2.61	3.39	5.02	1		
2	1.29	100	1.5%	100	1.0%	42	0.5%	0.15	0.15	0.015	12	6.59	7.85	10.11	33%	0.48	0.52	0.60	4.04	5.26	7.77	2	Possible Future Inlet Location	
3	1.95	59	1.4%	90	1.5%	428	0.5%	0.15	0.15	0.015	12	6.59	7.85	10.11	24%	0.43	0.47	0.54	5.46	7.18	10.72	3	Possible Future Inlet Location	
4	0.55	100	1.6%	112	1.6%	39	0.6%	0.15	0.15	0.015	11	6.81	8.11	10.42	34%	0.48	0.52	0.60	2.87	3.72	5.47	5		
5	0.91	100	2.0%	142	2.0%	165	0.6%	0.15	0.15	0.015	12	6.59	7.85	10.11	22%	0.48	0.52	0.60	2.87	3.72	5.47	5		
6	0.93	93	3.7%	95	2.3%	111	0.7%	0.15	0.15	0.015	8	7.58	8.99	11.47	35%	0.54	0.58	0.66	3.80	4.87	7.03	6	SUMP INLET #6	
7	1.04	60	2.9%	111	3.1%	141	0.8%	0.15	0.15	0.015	7	7.88	9.34	11.87	37%	0.55	0.59	0.67	4.46	5.71	8.21	7	SUMP INLET #7	
8A	0.23	12	2.0%			321	0.6%	0.15	0.15	0.015	5	8.57	10.13	12.79	78%	0.73	0.78	0.87	1.43	1.80	2.53	8A	COMBINED WITH 8B TO SUMP INLET #8	
8B	0.19	12	2.0%			233	0.8%	0.15	0.15	0.015	5	8.57	10.13	12.79	77%	0.73	0.77	0.86	1.18	1.49	2.08	8B	COMBINED WITH 8A TO SUMP INLET #8	
9	0.57	87	5.6%			112	0.9%	0.15	0.15	0.015	6	8.21	9.72	12.31	32%	0.52	0.57	0.64	2.45	3.14	4.52	9		
10	0.80	64	1.1%	121	1.1%	58	0.8%	0.15	0.15	0.015	10	7.05	8.38	10.74	31%	0.47	0.51	0.59	2.61	3.40	5.01	10		
11	0.98	77	2.0%	66	2.0%	170	0.8%	0.15	0.15	0.015	9	7.30	8.67	11.09	26%	0.50	0.54	0.62	3.56	4.59	6.69	11		
12	0.47	62	1.8%	134	1.7%	36	0.8%	0.15	0.15	0.015	8	7.58	8.99	11.47	36%	0.49	0.53	0.61	1.75	2.26	3.30	12		
13	0.43	58	1.6%	112	1.6%	90	0.8%	0.15	0.15	0.015	8	7.58	8.99	11.47	36%	0.50	0.54	0.62	1.64	2.11	3.08	13		
14	0.93	74	2.8%	135	1.8%	46	0.5%	0.15	0.15	0.015	8	7.58	8.99	11.47	41%	0.57	0.61	0.69	3.99	5.11	7.35	14		
15	0.47	75	0.5%			765	0.5%	0.15	0.15	0.015	10	7.05	8.38	10.74	78%	0.73	0.78	0.86	2.43	3.08	4.38	15		
16	0.91	100	2.5%	180	1.4%	144	0.5%	0.15	0.15	0.015	11	6.81	8.11	10.42	24%	0.43	0.47	0.55	2.65	3.47	5.15	16		
17	0.55	100	2.1%	356	1.4%	91	1.0%	0.15	0.15	0.015	13	6.39	7.61	9.62	16%	0.59	0.63	0.70	2.61	3.45	5.21	17		
18	1.98	100	2.2%	590	1.4%	67	1.0%	0.15	0.15	0.015	14	6.20	7.39	9.95	39%	0.48	0.52	0.60	2.67	3.68	6.68	18		
19	2.04	100	0.7%	357	0.8%	40	0.7%	0.15	0.15	0.015	15	6.02	7.18	9.30	15%	0.38	0.42	0.49	4.63	6.14	9.33	19		
20	0.80	100	0.8%	387	1.4%	10	1.4%	0.15	0.15	0.015	15	6.02	7.18	9.30	16%	0.39	0.43	0.50	1.85	2.44	3.71	20		
21	0.61	60	2.0%			420	0.9%	0.15	0.15	0.015	9	7.30	8.67	11.09	67%	0.68	0.73	0.81	3.04	3.86	5.51	21		
22	1.86	100	1.6%	118	2.7%	103	1.4%	0.15	0.15	0.015	11	6.81	8.11	10.42	80%	0.74	0.79	0.87	9.38	11.89	16.94	22	Possible Future Inlet Location	
23	2.13	63	1.5%	76	1.6%	427	2.5%	0.15	0.15	0.015	10	7.05	8.38	10.74	31%	0.47	0.51	0.59	7.00	9.10	13.41	23		
24	1.32	59	2.9%	134	2.2%	250	2.4%	0.15	0.15	0.015	7	7.88	9.34	11.87	42%	0.57	0.61	0.69	5.90	7.53	10.80	24		
25	1.74	41	2.4%	107	2.2%	382	2.4%	0.15	0.15	0.015	7	7.88	9.34	11.87	41%	0.57	0.61	0.69	7.76	9.91	14.22	25		
26	1.49	58	1.9%	98	1.7%	318	2.4%	0.15	0.15	0.015	8	7.58	8.99	11.47	42%	0.52	0.57	0.64	5.88	7.57	10.99	26		
27	0.73	57	1.5%	122	1.4%	148	0.5%	0.15	0.15	0.015	9	7.30	8.67	11.09	38%	0.50	0.54	0.62	2.68	3.46	5.05	27		
28	0.62	48	1.5%	133	1.4%	88	0.5%	0.15	0.15	0.015	8	7.58	8.99	11.47	40%	0.51	0.55	0.63	2.39	3.07	4.47	28		
29	0.78	49	1.6%	121	1.5%	205	0.5%	0.15	0.15	0.015	9	7.30	8.67	11.09	43%	0.53	0.57	0.65	2.99	3.85	5.60	29		
30	0.32	66	2.7%			61	0.7%	0.15	0.15	0.015	6	8.21	9.72	12.31	36%	0.54	0.58	0.66	1.42	1.82	2.61	30		
31	0.95	87	2.6%			300	0.5%	0.15	0.15	0.015	11	6.91	8.11	10.42	42%	0.57	0.61	0.69	3.70	4.74	6.88	31		
32	0.46	74	2.3%			133	0.6%	0.15	0.15	0.015	8	7.58	8.99	11.47	43%	0.57	0.62	0.70	2.00	2.56	3.67	32		
3																								